Montana Board of Oil and Gas Conservation Environmental Assessment

| Operator: Kykuit Resources, LLC Well Name/Number: Asbjornson 24-21-20 Location: SE NW Section 24 T21N R19E |
|--|
| County: Fergus , MT; Field (or Wildcat) Wildcat |
| · ———————————————————————————————————— |
| Air Quality |
| (possible concerns) |
| Long drilling time: No, 2 to 3 days drilling time. |
| Unusually deep drilling (high horsepower rig): No, small single derrick drilling rig TD 2200'. |
| Possible H2S gas production: None anticipated. |
| In/near Class I air quality area: Not in a Class I air quality area. |
| Air quality permit for flaring/venting (if productive): Yes, DEQ air quality permit required under |
| <u>75-2-211.</u> |
| Mitigation |
| Mitigation: _X Air quality permit (AQB review) |
| Gas plants/pipelines available for sour gas |
| Special equipment/procedures requirements |
| Other: |
| Comments: No, small single drilling rig TD 2200'. No concerns. |
| · · · · · · · · · · · · · · · · · · · |
| Water Quality |
| |
| (possible concerns) |
| (possible concerns) Salt/oil based mud: No, freshwater and freshwater mud system to be used. |
| (possible concerns) Salt/oil based mud: No, freshwater and freshwater mud system to be used. High water table: No, high water table expected. |
| (possible concerns) Salt/oil based mud: No, freshwater and freshwater mud system to be used. High water table: No, high water table expected. Surface drainage leads to live water: Yes, closest drainage is an unnamed ephemeral tributary |
| (possible concerns) Salt/oil based mud: No, freshwater and freshwater mud system to be used. High water table: No, high water table expected. Surface drainage leads to live water: Yes, closest drainage is an unnamed ephemeral tributary drainage to South Fork Cut Bank Creek, about 1/8 of a mile to the north of this location. Within |
| (possible concerns) Salt/oil based mud: _No, freshwater and freshwater mud system to be used High water table: _No, high water table expected Surface drainage leads to live water: _Yes, closest drainage is an unnamed ephemeral tributary drainage to South Fork Cut Bank Creek, about 1/8 of a mile to the north of this location. Within South Fork Cut Bank Creek is a large stock pond, about 1/8 of a mile to the west from this |
| (possible concerns) Salt/oil based mud: No, freshwater and freshwater mud system to be used. High water table: No, high water table expected. Surface drainage leads to live water: Yes, closest drainage is an unnamed ephemeral tributary drainage to South Fork Cut Bank Creek, about 1/8 of a mile to the north of this location. Within |
| (possible concerns) Salt/oil based mud: No, freshwater and freshwater mud system to be used. High water table: No, high water table expected. Surface drainage leads to live water: Yes, closest drainage is an unnamed ephemeral tributary drainage to South Fork Cut Bank Creek, about 1/8 of a mile to the north of this location. Within South Fork Cut Bank Creek is a large stock pond, about 1/8 of a mile to the west from this location. Water well contamination: No, closest water wells are about 5/8 of a mile to the east and 3/4 of a mile to the northwest of this location. Depth of these wells are 820' to 1480'. Surface hole will |
| (possible concerns) Salt/oil based mud: No, freshwater and freshwater mud system to be used. High water table: No, high water table expected. Surface drainage leads to live water: Yes, closest drainage is an unnamed ephemeral tributary drainage to South Fork Cut Bank Creek, about 1/8 of a mile to the north of this location. Within South Fork Cut Bank Creek is a large stock pond, about 1/8 of a mile to the west from this location. Water well contamination: No, closest water wells are about 5/8 of a mile to the east and 3/4 of a mile to the northwest of this location. Depth of these wells are 820' to 1480'. Surface hole will be drilled with freshwater to 150'. Steel surface casing will be run and cemented to surface to |
| (possible concerns) Salt/oil based mud: No, freshwater and freshwater mud system to be used. High water table: No, high water table expected. Surface drainage leads to live water: Yes, closest drainage is an unnamed ephemeral tributary drainage to South Fork Cut Bank Creek, about 1/8 of a mile to the north of this location. Within South Fork Cut Bank Creek is a large stock pond, about 1/8 of a mile to the west from this location. Water well contamination: No, closest water wells are about 5/8 of a mile to the east and 3/4 of a mile to the northwest of this location. Depth of these wells are 820' to 1480'. Surface hole will be drilled with freshwater to 150'. Steel surface casing will be run and cemented to surface to protect ground waters. If production is encountered 4 ½" casing will be run and cemented from |
| (possible concerns) Salt/oil based mud: No, freshwater and freshwater mud system to be used. High water table: No, high water table expected. Surface drainage leads to live water: Yes, closest drainage is an unnamed ephemeral tributary drainage to South Fork Cut Bank Creek, about 1/8 of a mile to the north of this location. Within South Fork Cut Bank Creek is a large stock pond, about 1/8 of a mile to the west from this location. Water well contamination: No, closest water wells are about 5/8 of a mile to the east and 3/4 of a mile to the northwest of this location. Depth of these wells are 820' to 1480'. Surface hole will be drilled with freshwater to 150'. Steel surface casing will be run and cemented to surface to protect ground waters. If production is encountered 4 ½" casing will be run and cemented from total depth to surface. |
| (possible concerns) Salt/oil based mud: No, freshwater and freshwater mud system to be used. High water table: No, high water table expected. Surface drainage leads to live water: Yes, closest drainage is an unnamed ephemeral tributary drainage to South Fork Cut Bank Creek, about 1/8 of a mile to the north of this location. Within South Fork Cut Bank Creek is a large stock pond, about 1/8 of a mile to the west from this location. Water well contamination: No, closest water wells are about 5/8 of a mile to the east and 3/4 of a mile to the northwest of this location. Depth of these wells are 820' to 1480'. Surface hole will be drilled with freshwater to 150'. Steel surface casing will be run and cemented to surface to protect ground waters. If production is encountered 4 ½" casing will be run and cemented from total depth to surface. Porous/permeable soils: No, sandy bentonitic soils. |
| (possible concerns) Salt/oil based mud: No, freshwater and freshwater mud system to be used. High water table: No, high water table expected. Surface drainage leads to live water: Yes, closest drainage is an unnamed ephemeral tributary drainage to South Fork Cut Bank Creek, about 1/8 of a mile to the north of this location. Within South Fork Cut Bank Creek is a large stock pond, about 1/8 of a mile to the west from this location. Water well contamination: No, closest water wells are about 5/8 of a mile to the east and 3/4 of a mile to the northwest of this location. Depth of these wells are 820' to 1480'. Surface hole will be drilled with freshwater to 150'. Steel surface casing will be run and cemented to surface to protect ground waters. If production is encountered 4 ½" casing will be run and cemented from total depth to surface. Porous/permeable soils: No, sandy bentonitic soils. Class I stream drainage: No, Class I stream drainages nearby. |
| Salt/oil based mud: No, freshwater and freshwater mud system to be used. High water table: No, high water table expected. Surface drainage leads to live water: Yes, closest drainage is an unnamed ephemeral tributary drainage to South Fork Cut Bank Creek, about 1/8 of a mile to the north of this location. Within South Fork Cut Bank Creek is a large stock pond, about 1/8 of a mile to the west from this location. Water well contamination: No, closest water wells are about 5/8 of a mile to the east and 3/4 of a mile to the northwest of this location. Depth of these wells are 820' to 1480'. Surface hole will be drilled with freshwater to 150'. Steel surface casing will be run and cemented to surface to protect ground waters. If production is encountered 4 ½' casing will be run and cemented from total depth to surface. Porous/permeable soils: No, sandy bentonitic soils. Class I stream drainage: No, Class I stream drainages nearby. Mitigation: |
| (possible concerns) Salt/oil based mud: No, freshwater and freshwater mud system to be used. High water table: No, high water table expected. Surface drainage leads to live water: Yes, closest drainage is an unnamed ephemeral tributary drainage to South Fork Cut Bank Creek, about 1/8 of a mile to the north of this location. Within South Fork Cut Bank Creek is a large stock pond, about 1/8 of a mile to the west from this location. Water well contamination: No, closest water wells are about 5/8 of a mile to the east and 3/4 of a mile to the northwest of this location. Depth of these wells are 820' to 1480'. Surface hole will be drilled with freshwater to 150'. Steel surface casing will be run and cemented to surface to protect ground waters. If production is encountered 4 ½" casing will be run and cemented from total depth to surface. Porous/permeable soils: No, sandy bentonitic soils. Class I stream drainage: No, Class I stream drainages nearby. Mitigation: Lined reserve pit |
| (possible concerns) Salt/oil based mud: No, freshwater and freshwater mud system to be used. High water table: No, high water table expected. Surface drainage leads to live water: Yes, closest drainage is an unnamed ephemeral tributary drainage to South Fork Cut Bank Creek, about 1/8 of a mile to the north of this location. Within South Fork Cut Bank Creek is a large stock pond, about 1/8 of a mile to the west from this location. Water well contamination: No, closest water wells are about 5/8 of a mile to the east and 3/4 of a mile to the northwest of this location. Depth of these wells are 820' to 1480'. Surface hole will be drilled with freshwater to 150'. Steel surface casing will be run and cemented to surface to protect ground waters. If production is encountered 4 ½' casing will be run and cemented from total depth to surface. Porous/permeable soils: No, sandy bentonitic soils. Class I stream drainage: No, Class I stream drainages nearby. Mitigation: Lined reserve pit X Adequate surface casing |
| (possible concerns) Salt/oil based mud: _No, freshwater and freshwater mud system to be used |
| (possible concerns) Salt/oil based mud: No, freshwater and freshwater mud system to be used. High water table: No, high water table expected. Surface drainage leads to live water: Yes, closest drainage is an unnamed ephemeral tributary drainage to South Fork Cut Bank Creek, about 1/8 of a mile to the north of this location. Within South Fork Cut Bank Creek is a large stock pond, about 1/8 of a mile to the west from this location. Water well contamination: No, closest water wells are about 5/8 of a mile to the east and 3/4 of a mile to the northwest of this location. Depth of these wells are 820' to 1480'. Surface hole will be drilled with freshwater to 150'. Steel surface casing will be run and cemented to surface to protect ground waters. If production is encountered 4 ½' casing will be run and cemented from total depth to surface. Porous/permeable soils: No, sandy bentonitic soils. Class I stream drainage: No, Class I stream drainages nearby. Mitigation: Lined reserve pit X. Adequate surface casing Berms/dykes, re-routed drainage Closed mud system |
| (possible concerns) Salt/oil based mud: _No, freshwater and freshwater mud system to be used |

Soils/Vegetation/Land Use

| (possible concerns) |
|---|
| Steam crossings: No, streams to be crossed, only ephemeral drainages |
| High erosion potential: No, small cut up to 4.7' and small fill up to 4.4', required. |
| Loss of soil productivity: No, location will be restored after drilling, if nonproductive. If |
| productive unused portion of drillsite will be reclaimed. |
| Unusually large wellsite: No, small drillsite, 200'X200'. |
| Damage to improvements: None, surface use is cultivated land. |
| Conflict with existing land use/values: Slight |
| Mitigation |
| Avoid improvements (topographic tolerance) |
| Exception location requested |
| X Stockpile topsoil |
| Stream Crossing Permit (other agency review) |
| X Reclaim unused part of wellsite if productive |
| Special construction methods to enhance reclamation |
| Other |
| Comments: Will utilize existing county, Knox Ridge and 2 Calf Road and existing ranch |
| trails. Short access off existing ranch trail to be build, about 3/8 of a mile of new access will be |
| built into this location. Unlined earthen pits will be utilized for drilling. Drilling fluids will used |
| to seal surface owners stock pond. Solids will be allowed to dry in the pits. When pits are dry |
| they will be filled in with subsoil and topsoil spread. |
| |
| Health Hazards/Noise |
| Health Hazarus/Noise |
| (possible concerns) |
| Proximity to public facilities/residences: <u>Closest residences are about 1 mile to the northeast.</u> |
| The town of Winifred, about 8.5 miles to the southwest of this location. |
| |
| Possibility of H2S: No, none anticipated. |
| Size of rig/length of drilling time: Small single derrick drilling rig/Short drilling time 2 to 3 days. |
| Size of rig/length of drilling time: Small single derrick drilling rig/Short drilling time 2 to 3 days. Mitigation: |
| Size of rig/length of drilling time: Small single derrick drilling rig/Short drilling time 2 to 3 days. Mitigation: _X Proper BOP equipment |
| Size of rig/length of drilling time: Small single derrick drilling rig/Short drilling time 2 to 3 days. Mitigation: _X Proper BOP equipment _ Topographic sound barriers |
| Size of rig/length of drilling time: Small single derrick drilling rig/Short drilling time 2 to 3 days. Mitigation: _X Proper BOP equipment _ Topographic sound barriers _ H2S contingency and/or evacuation plan |
| Size of rig/length of drilling time: Small single derrick drilling rig/Short drilling time 2 to 3 days. Mitigation: _X Proper BOP equipment _ Topographic sound barriers _ H2S contingency and/or evacuation plan _ Special equipment/procedures requirements |
| Size of rig/length of drilling time: Small single derrick drilling rig/Short drilling time 2 to 3 days. Mitigation: _X Proper BOP equipment _ Topographic sound barriers _ H2S contingency and/or evacuation plan _ Special equipment/procedures requirements _ Other: |
| Size of rig/length of drilling time: Small single derrick drilling rig/Short drilling time 2 to 3 days. Mitigation: _X Proper BOP equipment _ Topographic sound barriers _ H2S contingency and/or evacuation plan _ Special equipment/procedures requirements _ Other: Comments: Adequate amount of surface casing and BOP equipment should mitigate |
| Size of rig/length of drilling time: Small single derrick drilling rig/Short drilling time 2 to 3 days. Mitigation: _X Proper BOP equipment _ Topographic sound barriers _ H2S contingency and/or evacuation plan _ Special equipment/procedures requirements _ Other: |
| Size of rig/length of drilling time: Small single derrick drilling rig/Short drilling time 2 to 3 days. Mitigation: _X Proper BOP equipment _ Topographic sound barriers _ H2S contingency and/or evacuation plan _ Special equipment/procedures requirements _ Other: Comments: Adequate amount of surface casing and BOP equipment should mitigate |
| Size of rig/length of drilling time: Small single derrick drilling rig/Short drilling time 2 to 3 days. Mitigation: _X Proper BOP equipment _ Topographic sound barriers _ H2S contingency and/or evacuation plan _ Special equipment/procedures requirements _ Other: Comments: Adequate amount of surface casing and BOP equipment should mitigate any problems. Wildlife/recreation (possible concerns) |
| Size of rig/length of drilling time: Small single derrick drilling rig/Short drilling time 2 to 3 days. Mitigation: _X Proper BOP equipment _ Topographic sound barriers _ H2S contingency and/or evacuation plan _ Special equipment/procedures requirements _ Other: _ Comments: Adequate amount of surface casing and BOP equipment should mitigate any problems. Wildlife/recreation (possible concerns) Proximity to sensitive wildlife areas (DFWP identified): None identified. |
| Size of rig/length of drilling time: Small single derrick drilling rig/Short drilling time 2 to 3 days. Mitigation: X Proper BOP equipment Topographic sound barriers H2S contingency and/or evacuation plan Special equipment/procedures requirements Other: Comments: Adequate amount of surface casing and BOP equipment should mitigate any problems. Wildlife/recreation (possible concerns) Proximity to sensitive wildlife areas (DFWP identified): None identified. Proximity to recreation sites: None identified. |
| Size of rig/length of drilling time: Small single derrick drilling rig/Short drilling time 2 to 3 days. Mitigation: _X Proper BOP equipment _ Topographic sound barriers _ H2S contingency and/or evacuation plan _ Special equipment/procedures requirements _ Other: _ Comments: Adequate amount of surface casing and BOP equipment should mitigate any problems. Wildlife/recreation (possible concerns) Proximity to sensitive wildlife areas (DFWP identified): None identified. Proximity to recreation sites: None identified. Creation of new access to wildlife habitat: None |
| Size of rig/length of drilling time: Small single derrick drilling rig/Short drilling time 2 to 3 days. Mitigation: X Proper BOP equipment Topographic sound barriers H2S contingency and/or evacuation plan Special equipment/procedures requirements Other: Comments: Adequate amount of surface casing and BOP equipment should mitigate any problems. Wildlife/recreation (possible concerns) Proximity to sensitive wildlife areas (DFWP identified): None identified. Proximity to recreation sites: None identified. Creation of new access to wildlife habitat: None Conflict with game range/refuge management: None |
| Size of rig/length of drilling time: Small single derrick drilling rig/Short drilling time 2 to 3 days. Mitigation: _X Proper BOP equipment _ Topographic sound barriers _ H2S contingency and/or evacuation plan _ Special equipment/procedures requirements _ Other: _ Comments: Adequate amount of surface casing and BOP equipment should mitigate any problems. Wildlife/recreation (possible concerns) Proximity to sensitive wildlife areas (DFWP identified): None identified. Proximity to recreation sites: None identified. Creation of new access to wildlife habitat: None Conflict with game range/refuge management: None Threatened or endangered Species: Threatened or endangered species identified are the Pallid |
| Size of rig/length of drilling time: Small single derrick drilling rig/Short drilling time 2 to 3 days. Mitigation: X Proper BOP equipment Topographic sound barriers H2S contingency and/or evacuation plan Special equipment/procedures requirements Other: Comments: Adequate amount of surface casing and BOP equipment should mitigate any problems. Wildlife/recreation (possible concerns) Proximity to sensitive wildlife areas (DFWP identified): None identified. Proximity to recreation sites: None identified. Creation of new access to wildlife habitat: None Conflict with game range/refuge management: None |

| Avoidance (topographic tolerance/exception) Other agency review (DFWP, federal agencies, DSL) |
|---|
| Screening/fencing of pits, drillsite |
| Other: Comments: Surface is cultivated private land. No concerns. |
| |
| Historical/Cultural/Paleontological (possible concerns) |
| Proximity to known sites None identified |
| Mitigation avoidance (topographic tolerance, location exception) |
| other agency review (SHPO, DSL, federal agencies) Other: |
| Comments: Surface is cultivated private land. No concerns. |
| Social/Economic |
| (possible concerns) |
| Substantial effect on tax base |
| Create demand for new governmental servicesPopulation increase or relocation |
| Comments: No, impact expected from the drilling of this well. |
| Remarks or Special Concerns for this site |
| No special concerns about this wellsite. This is a Colorado Formation test to be drilled to 2200' TD. |
| Summary: Evaluation of Impacts and Cumulative effects |
| No significant or long term impacts expected from the drilling of this well. Some short term impacts will occur. |
| |
| |
| I conclude that the approval of the subject Notice of Intent to Drill (does/ <u>does not</u>) constitute a major action of state government significantly affecting the quality of the human environment, and (does/ <u>does not</u>) require the preparation of an environmental impact statement. |
| Prepared by (BOGC): /s/ Steven Sasaki |
| (title:) Chief Field Inspector |
| Date: May 21, 2010 |
| Other Persons Contacted: |

| Montana Bureau of Mines and Geology, GWIC website |
|--|
| (Name and Agency) |
| Fergus County water wells |
| (subject discussed) |
| May 21, 2010 |
| (date) |
| |
| US Fish and Wildlife, Region 6 website |
| (Name and Agency) |
| ENDANGERED, THREATENED, PROPOSED AND CANDIDATE SPECIES MONTANA |
| COUNTIES, Fergus County |
| (subject discussed) |
| _May 21, 2010 |
| (date) |
| |
| Ms. Windy Davis, Montana FWP |
| (Name and Agency) |
| Greater Sage Grouse Lecks in Fergus County, Montana |
| (subject discussed) |
| _May 21, 2010 |
| (date) |
| TC1 |
| If location was inspected before permit approval: |
| Inspection date: |
| Inspector: |
| Others present during inspection: |