

#### TONGUE RIVER DAM

#### Fact Sheet

### **PROJECT DESCRIPTION**

- ◆ Located on the Tongue River in Big Horn County, 5 miles north of Decker
- ♦ Construction completed in 1940
- Owned by DNRC & managed by the SWPB
- ♦ Operated by the Tongue River Water Users Association since 1940
- ◆ Project consists of:
  - Zoned Earthfill Dam, 93 feet high, 1,824 feet long
  - Uncontrolled, 150 feet wide, 560 feet long concrete labyrinth weir principal spillway. Auxillary spillway consists of






- 16-foot horseshoe-shaped concrete auxiliary outlet tunnel; downstream and upstream wet wells with a 4.5 ft x 7.5 ft fixed wheel guard gate and a 4.5 ft x 7.5 ft cast iron sluice gate
- Stores 79,071 acre-feet at normal full pool, covering 3,700 surface acres.
- ♦ The dam is a "high hazard" structure, which means that its failure could cause loss of life. Farms and ranches, roads, bridges, and utilities are located in the flood plain.

### **WATER USE**

- ♦ 40,000 acre-feet through 180 contracts; provides a portion of the Northern Cheyenne Tribe's federally reserved water right
- ♦ Irrigation, industrial, fish hatchery

• A very popular recreation site, with Tongue River State Park, managed under lease by the MT Fish, Wildlife and Parks, located on the west shore of the reservoir.





## **REHABILITATION SUMMARY**

From 1996 to 1999, the DNRC completed a major rehabilitation of the dam. The rehabilitation included:

- Raising the spillway crest an additional 4-feet, providing up to an additional 14,000 acre-feet of storage
- Construction of a new primary low level outlet tunnel and auxiliary spillway
- Replacing the principal spillway
- ♦ Improvements to the drain system
- ♦ Improvement to access and maintenance roads
- New gates for existing low level outlet conduit
- Rehabilitation cost (1999): \$48,000,000

# **FUTURE NEEDS**

- The dam was rehabilitated in 1996 to 1999 and meets or exceeds existing dam safety standards. No deficiencies currently exist.
- Determine a long-term solution to the auxiliary spillway chute concrete step cracking.
- A plan is currently being developed to repair abutment erosion below the right spillway wing-wall.
- Finalize plans to mitigate cavitation issues in the auxiliary low level outlet operating gate chamber

Gatehouse and top of spillway



Outlet and spillway

